



# MAIN FLOOR PLAN

977.0 SQ. FT.  
1404.24 TOTAL SQ. FT.

ALL INTERIOR AND EXTERIOR RAKED WALLS ARE TO BE FRAMED FULL HEIGHT w/ BLOCKING @ 8'-0" o.c.  
STUDS EXCEEDING 20' IN LENGTH ARE TO BE 2-2x LAMINATED STUDS w/ STAGGERED JOINTS

- - INDICATES GULLAM POST
- - INDICATES NAIL-LAM POST (SOLID BEARING)
- - INDICATES POINT LOAD
- ▨ - INDICATES 1x6 T&G V-JOINT PINE LINER